



INSTALLATION PRECHECK LIST

TO BE USED IN CONJUNCTION OF CORRESPONDING MACHINE MODEL INSTALLATION SPEC SHEET

- Confirm adequate counter space and hole for machine. Allow for 6-8 inches of space around machine.
- Confirm power receptacle location is within 5 feet of machine. Confirm receptacle matches included/recommended plug type.
- CONFIRM 208-240V BETWEEN BOTH HOT LEGS ON RECEPTACLE. CONFIRM 120V BETWEEN HOT LEG AND GROUND. NEUTRAL LINE IS NOT UTILIZED.**
- Confirm cold water supply and shut off valve is within 5 feet of machine.
- Confirm water pressure and quality specifications correspond to recommended values.
- FLUSH WATER LINE & FILTRATION FOR MINIMUM OF 5 GALLONS / 5 MINUTES PRIOR TO CONNECTING TO MACHINE.**
- Confirm an open gravity drain within 4 feet of machine with a minimum diameter of 2 inches.
- Review, fill out and submit warranty terms and conditions attached to installation spec sheet to tech@sanremous.com